

FENCE REPAIR AND NEW INSTALLATION

Unit Rate Pricing Bid Form

No.	Description	Quantity (2)	Unit	Item Cost (3)
REPAIR (1)				
	See Note 4 below			
1	Six (6') foot 2.875" OD Steel Corner Post including caps	1	EA	\$25.00
2	Six (6') foot 2.375" OD Steel Line Post including caps	1	EA	\$23.00
3	Six (6') foot 4.0 OD Steel Gate/Corner Post including caps	1	EA	\$94.00
4	Eight (8') foot 2.875" OD Steel Corner Post including caps	1	EA	\$34.00
5	Eight (8') foot 2.375" OD Steel Liner Post in caps	1	EA	\$31.00
6	Eight (8') foot 4.0 OD Steel Gate/Corner Post including caps	1	EA	\$125.00
7	Top Rail and ties	1	LF	\$2.50
8	PVC Fence Fabric, two (2") inch mesh, Six (6') Foot including tension bar and tension wire (1)	1	LF	\$4.20
9	PVC Fence Fabric, two (2") inch mesh, Eight (8') Foot including tension bar and tension wire (1)	1	LF	\$5.59
10	PVC Fence Fabric, one (1") mesh, Six (6') Foot including tension bar and tension wire (1)	1	LF	\$14.00
11	PVC Fence Fabric, two (1") mesh, Eight (8') Foot including tension bar and tension wire (1)	1	LF	\$16.00
12	Six (6') swing gate	1	EA	\$700.00
13	Four (4') foot padlockable pedestrian gate	1	EA	\$450.00
14	Twenty (20') rolling gate	1	EA	\$1,975.00
15	Three strand barbed wire	1	LF	\$0.55
16	Electrical Grounds	1	EA	\$25.00
17	Complete new lift station fence installation, forty (40') by forty (40')	1	EA	\$10,278.00

Note 1 The minimum liner footage for fence fabric will be ten (10') feet.

Note 2 Quantities shown are for illustrative purposes and to establish a unit price for each specific item and do not necessarily represent the quantities of any specific work assignment that might result from this solicitation.

Note 3 If renewals of the contract are executed the unit prices shall be increased by the most recent 12-month percentage change All Items, as published by the United States Department of Labor, Bureau of Labor Statistics, <https://www.bls.gov/cpi/>.

Note 4 All materials shall be in compliance with 321040 of the Specifications and Details in this procurement

Note 5 Removal and disposal of any existing fence is incidental to the new or repaired fence construction and there is no separate bid item for existing fence removal and disposal. Cost should be included in each line item.

Note 6 The cost of clearing, removing and disposing of the material shall not constitute a separate bid item and shall be considered incidental to fence construction/repair.

Work Assignment 2 - Hurricane Ian Plant and Booster Station Fence Repairs					
Plant/Booster Station	Repairs Needed	Quantity	Unit	Unit Cost	Plant/Booster Total
Northeast Booster	Replace damaged barb wire arms (2). 12 feet of PVC coated 6' high fence, add ties to post and add brace and end cup. Straighten and reset posts on approximately 20 ft of fence.	1	EA		\$895.00
Hillsborough Booster	Full replacement of 8-foot PVC coated fence including all posts, gates, and three-strand barbed wire. Includes replacing (1) rolling gate 20-feet and (1) 4 foot lockable pedestrian gate.	1	EA		\$30,984.00
Myakkahatchee Creek Water Treatment Plant	636 ft of 8-foot PVC coated fence with three-strand barbed wire, including (1) 22-foot cantilever gate, (1) 4-foot lockable pedestrian gate and (1) 8-foot high double gate approximately 16-feet wide (to be confirmed by contractor), and all posts. Reattach gate operator to gate. Three hundred (300') feet of 8-foot PVC coated fence on right side of driveway, straighten second cantilever gate and gate posts and fix/reattach gate opener. Replace 40 feet of top rail on the back left corner. Replace posts on approximately 200 feet of leaning fence on the South side of property.	1	EA		\$63,180.00
Pan American Wastewater Treatment Plant	Repair and retie existing 450 ft of 8 foot PVC coated one-inch mesh fence. Replace approximately 300 ft of damaged top rail, straighten and repair existing gate and gate posts.	1	EA		\$14,830.00
				Total Lift Station Repair Cost:	\$109,889.00

Note 1: All materials shall be in compliance with 321040 of the Specifications and Details in this procurement

Note 2: Removal and disposal of any existing fence is incidental to the new or repaired fence construction and there is no separate bid item for existing fence removal and disposal. Cost should be included in each line item.

Note 3: The cost of clearing, removing and disposing of the material shall not constitute a separate bid item and shall be considered incidental to fence construction/repair.