

**FIRST AMENDMENT TO CONTRACT NO. 2023-34 FENCE REPAIR AND NEW INSTALLATION FOR
CONFORMITY TO LIFT STATION SPECIFICATIONS AND STANDARDS**

This *First Amendment* to Contract No. 2023-34 for Fence Repair and New Installation is to ensure conformance to lift station specifications and standards (“First Amendment”), is made and entered into by and between the City of North Port, Florida, a municipal corporation of the State of Florida and whose address is 4970 City Hall Boulevard, North Port, Florida 34286 (“City”) and Jay’s Fencing LLC, which is registered to conduct business in the State of Florida and whose address is 2059 19th Street Sarasota, FL 34234 (“Contractor”).

RECITALS

WHEREAS, on or around January 9, 2024, the parties entered into a Contract No. 2023-34 for *Fence Repair and New Installation for Lift Station, Booster Stations, and Plant Fencing Repairs and/or New Installations* (the “Original Contract”); and

WHEREAS, Specification Section 336020 for Standard Lift Stations - FENCE AND GATES, requires the installation of double height eight-foot gates (total sixteen (16) foot width), and the parties mutually desire to amend the Original Contract to include a line item for this gate; and

NOW THEREFORE, in consideration of the mutual covenants contained herein, the sufficiency and receipt of which are acknowledged, the parties agree that the Original Contract is amended as follows, with all other terms in the Original Contract remaining unchanged and in full force and effect:

1. EFFECT OF AMENDMENT/EFFECTIVE DATE

- A. The parties ratify the terms and conditions of the Original Contract not inconsistent with this First Amendment, all of which are incorporated by reference as if set forth fully herein. This First Amendment modifies the sections of the Original Contract as identified herein. Where a section of the Original Contract is not identified, the terms as they appear in the Original Contract remain and apply.
- B. All references to this “Contract” in the Original Contract and this First Amendment mean and include both the Original Contract and this First Amendment.
- C. This First Amendment is effective as of the date the last party approves or executes it, as applicable (the “Effective Date”), and shall continue as otherwise provided in the Original Contract.

2. NEW EXHIBIT B-1 – SPECIFICATIONS

Exhibit B-1, attached, replaces Exhibit B, and is incorporated as if set forth in the Agreement.

3. NEW EXHIBIT C-1 – FEE SCHEDULE

Exhibit C-1, attached, replaces Exhibit C, and is incorporated as if set forth in the Agreement.

IN WITNESS WHEREOF, the parties have executed this First Amendment as follows.

JAY'S FENCING, LLC

By: *[Signature]*
Name: James Miller
Title: President

ACKNOWLEDGEMENT

STATE OF Florida
COUNTY OF Sarasota

The foregoing instrument was acknowledged before me by means of physical presence or online notarization, this 13 day of June 2024, by James Jay Miller (name), as president (title) for Jay's Fencing (entity).

[Signature]
Notary Public

Personally Known OR Produced Identification
Type of Identification Produced _____



Approved by the City Commission of the City of North Port, Florida on _____, 2024.

CITY OF NORTH PORT, FLORIDA

A. JEROME FLETCHER II, ICMA-CM, MPA
CITY MANAGER

ATTEST

HEATHER FAUST, MMC
CITY CLERK

APPROVED AS TO FORM AND CORRECTNESS

AMBER L. SLAYTON, B.C.S.
CITY ATTORNEY

SECTION 321040

CHAIN LINK FENCE

PART 1 - GENERAL

1.1 SCOPE

- A. This item shall consist of furnishing and erecting a chain link fence in accordance with these specifications, the details shown on the plans, and in conformity with the lines and grades shown on the plans.

1.2 GENERAL

A. WORK INCLUDED

The Contractor shall, unless otherwise specified, furnish all labor, materials, equipment, tools, and all other associated appurtenances necessary to do the work required under the contract.

- B. LOCATION OF THE WORK: The location of the work is as shown on the Plans.

C. COORDINATION OF THE WORK

The Contractor shall be responsible for the satisfactory coordination of the installation of the fence with other construction and activities in the area. Delays in work resulting from lack of such harmony shall not in any way be a cause for extra compensation by any of the parties.

1.3 METHOD OF MEASUREMENT AND PAYMENT

The work shall be measured, and the compensation determined in the following manner.

A. CHAIN LINK FENCE

1. The chain link fence will be measured for payment by the linear foot. Measurement will be along the top of the fence from center to center of end posts, excluding the length occupied by gate openings. Removal and disposal of any existing fence is incidental to the new fence construction and there is no separate bid item for existing fence removal and disposal, unless otherwise indicated in the project documents.

B. GATES

1. Gates will be measured as complete units. Removal and disposal of any existing gates is incidental to the new fence and gate construction and there is no separate bid item for existing fence gate removal and disposal, unless otherwise indicated in the project documents.

1.4 REFERENCED STANDARDS (LATEST REVISION)

A. ASTM Standards

1. ASTM A121 Standard Specification for Metallic-Coated Carbon Steel Barbed Wire
2. ASTM A153 Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware
3. ASTM A392 Standard Specification for Zinc-Coated Steel Chain-Link Fence Fabric
4. ASTM A491 Standard Specification for Aluminum-Coated Steel Chain-Link Fence Fabric
5. ASTM A824 Standard Specification for Metallic-Coated Steel Marcellled Tension Wire for Use with Chain Link Fence
6. ASTM B117 Standard Practice for Operating Salt Spray (Fog) Apparatus
7. ASTM F567 Standard Practice for Installation of Chain-Link Fence
8. ASTM F668 Standard Specification for Polyvinyl Chloride (PVC), Polyolefin and other Organic Polymer Coated Steel Chain-Link Fence Fabric
9. ASTM F1043 Standard Specification for Strength and Protective Coatings on Steel Industrial Fence Framework
10. ASTM F1083 Standard Specification for Pipe, Steel, Hot-Dipped Zinc-Coated (Galvanized) Welded, for Fence Structures
11. ASTM F1183 Standard Specification for Aluminum Alloy Chain Link Fence Fabric
12. ASTM F1345 Standard Specification for Zinc 5% Aluminum-Mischmetal Alloy Coated Steel Chain-Link Fence Fabric

13. ASTM G152 Standard Practice for Operating Open Flame Carbon Arc Light Apparatus for Exposure of Nonmetallic Materials
14. ASTM G153 Standard Practice for Operating Enclosed Carbon Arc Light Apparatus for Exposure of Nonmetallic Materials
15. ASTM G154 Standard Practice for Operating Fluorescent Ultraviolet (UV) Lamp Apparatus for Exposure of Nonmetallic Materials
16. ASTM G155 Standard Practice for Operating Xenon Arc Light Apparatus for Exposure of Nonmetallic Materials

B. Federal Specifications (FED SPEC)

1. FED SPEC RR-F-191/3 Fencing, Wire and Post, Metal (Chain-Link Fence Posts, Top Rails and Braces)
2. FED SPEC RR-F-191/4 Fencing, Wire and Post, Metal (Chain-Link Fence Accessories)

1.5 SUBMITTALS

- A. The Contractor shall submit in writing documentation to justify approval of these materials by NPU prior to the start of the project.

The Contractor submittals shall include the statement that the submittals have been reviewed and the materials meet the contract specifications and/or NPU Standard Details.

For materials that the Contractor is requesting deviations from this specification and/or NPU Standard Details, the Contractor shall submit in writing a minimum of 60 days prior to construction, documentation to justify approval of these materials by NPU.

No fabrication shall take place until the final shop drawings are reviewed by Engineer and NPU. Final approval is at the discretion of NPU.

PART 2 - PRODUCTS

2.1 MATERIALS

The materials used in this work shall be all new and conform to the requirements for class, kind, size and material as specified below.

- A. Fabric

1. The fabric shall six foot (6') or eight foot (8') high with woven 9-gauge black polyvinyl chloride (PVC)-coated steel wire in a 1" or 2" (one or two-inch) mesh, as shown on the plans and/or project bid form, and shall meet the requirements of ASTM F668, Class 2b. The fabric shall be woven from a 9-gauge aluminum-coated steel wire in a 1" or 2" (one or two-inch) mesh and shall conform to the requirements of ASTM A491.

B. Barbed Wire

1. Barbed wire shall be 3 (three) strand 12-1/2 gauge zinc-coated wire with 4 (four) point barbs and shall conform to the requirements of ASTM A121, Class 3, Chain Link Fence Grade.

C. Posts, Rails, and Braces: Line posts, rails, and braces shall conform to the requirements of ASTM F1043 or ASTM F1083 as follows:

1. Galvanized tubular steel pipe shall conform to the requirements of Group IA, (Schedule 40) coatings conforming to Type A, or Group IC (High Strength Pipe), External coating Type B, and internal coating Type B or D.
2. The dimensions of the posts, rails, and braces shall be in accordance with Tables I through VI of Federal Specification RR-F-191/3.

D. Gates: Gate frames shall consist of polymer-coated steel pipe and shall conform to the specifications for the same material under paragraph 162-2.3. The fabric shall be of the same type material as used in the fence.

E. Wire Ties and Tension Wires: Wire ties for use in conjunction with a given type of fabric shall be of the same material and coating weight identified with the fabric type. Tension wire shall be seven (7) gauge marcelled steel wire with the same coating as the fabric type and shall conform to ASTM A824. All material shall conform to Federal Specification RR-F-191/4.

F. Miscellaneous Fittings and Hardware: Miscellaneous steel fittings and hardware for use with zinc-coated steel fabric shall be of commercial grade steel or better quality, wrought or cast as appropriate to the article, and sufficient in strength to provide a balanced design when used in conjunction with fabric posts, and wires of the quality specified herein. All steel fittings and hardware shall be protected with a zinc coating applied in conformance with ASTM A153. Barbed wire support arms shall withstand a load of 250 pounds applied vertically to the outermost end of the arm.

- G. Concrete: Concrete shall have a minimum 28-day compressive strength of 3,000 psi.
- H. Marking: Each roll of fabric shall carry a tag showing the kind of base metal (steel, aluminum, or aluminum alloy number), kind of coating, the gauge of the wire, the length of fencing in the roll, and the name of the manufacturer. Posts, wire, and other fittings shall be identified as to manufacturer, kind of base metal (steel, aluminum, or aluminum alloy number), and kind of coating.

PART 3 – EXECUTION

3.1 INSTALLATION

- A. General: The fence shall be constructed in accordance with the details on the plans and as specified here using new materials. All work shall be performed in a manner satisfactory to the City. The Contractor shall establish and mark the property line or fence line for the work. The Contractor shall layout the fence line based on the plans. The Contractor shall also span the opening below the fence with barbed wire at all locations where it is not practical to conform the fence to the general contour of the ground surface because of natural or manmade features such as drainage ditches. The new fence shall be permanently tied to the terminals of existing fences as shown on the plans. The Contractor shall stake down the woven wire fence at several points between posts as shown on the plans. The Contractor shall arrange the work so that construction of the new fence will immediately follow the removal of existing fences. The length of unfenced section at any time shall not exceed 300 feet. The work shall progress in this manner and at the close of the working day the newly constructed fence shall be tied to the existing fence.
- B. Clearing the Fence Line: Clearing shall consist of the removal of all stumps, brush, rocks, trees, or other obstructions that will interfere with proper construction of the fence. Stumps within the cleared area of the fence shall be grubbed or excavated. The bottom of the fence shall be placed a uniform distance above ground, as specified in the plans. When shown on the plans or as directed by the City or the Engineer, the existing fences and gates which interfere with the new fence location shall be removed by the Contractor as a part of the construction work unless such removal is listed as a separate item in the bid schedule. All holes remaining after post and stump removal shall be refilled with suitable soil, gravel, or other suitable material and compacted with tampers. The cost of clearing, removing and disposing of the material shall not constitute a separate bid item and shall be considered incidental to fence construction.

- C. Installing Posts: All posts shall be set in concrete at the required dimension and depth and at the spacing shown on the plans.
1. The concrete shall be thoroughly compacted around the posts by tamping or vibrating and shall have a smooth finish slightly higher than the ground and sloped to drain away from the posts. All posts shall be set plumb and to the required grade and alignment. No materials shall be installed on the posts, nor shall the posts be disturbed in any manner within seven (7) days after the individual post footing is completed. Should rock be encountered at a depth less than the planned footing depth, a hole two (2) inches larger than the greatest dimension of the posts shall be drilled to a depth of twelve (12) inches. After the posts are set, the remainder of the drilled hole shall be filled with grout, composed of one-part Portland cement and two parts mortar sand. Any remaining space above the rock shall be filled with concrete in the manner described above. In lieu of drilling, the rock may be excavated to the required footing depth. No extra compensation shall be made for rock excavation.
 2. Posts should be spaced not more than ten (10) feet apart and should be set a minimum of 36 inches in concrete footings. The post holes shall be in proper alignment so that there is a minimum of three (3) inches of concrete on all sides of the posts.
- D. Installing Top Rails: The top rail shall be continuous and shall pass through the post tops. The coupling used to join the top rail lengths shall allow for expansion.
- E. Installing Braces: Horizontal brace rails, with diagonal truss rods and turnbuckles, shall be installed at all terminal posts.
- F. Installing Fabric: The wire fabric shall be firmly attached to the posts and braced as shown on the plans. All wire shall be stretched taut and shall be installed to the required elevations. The fence shall generally follow the contour of the ground, with the bottom of the fence fabric no less than one (1) inch or more than four (4) inches from the ground surface. Grading shall be performed where necessary to provide a neat appearance. At locations of small natural swales or drainage ditches and where it is not practical to have the fence conform to the general contour of the ground surface, longer posts may be used and multiple strands of barbed wire stretched to span the opening below the fence. The vertical clearance between strands of barbed wire shall be six (6) inches or less.

Openings below the fence may also be spanned with barbed wire fastened to stakes.

The Engineer shall specify if tension wire is to be installed.

- G. Electrical Grounds: Electrical grounds shall be constructed [where a power line passes over the fence] [at 500 feet intervals]. [The ground shall be installed directly below the point of crossing.] The ground shall be accomplished with a copper clad rod eight (8) feet long and a minimum of five-eighths (5/8) inches in diameter driven vertically until the top is six (6) inches below the ground surface. A No. 6 solid copper conductor shall be clamped to the rod and to the fence in such a manner that each element of the fence is grounded. Installation of ground rods shall not constitute a separate bid item and shall be considered incidental to fence construction.

The Engineer shall indicate the location of all electrical grounds on the plans. Grounding may not be necessary with the use of composite posts.

- H. Cleaning up: The Contractor shall remove from the vicinity of the completed work all tools, buildings, equipment, etc., used during construction. All disturbed areas shall be seeded and/or sodded per NPU Standard Specification, 321030 Restoration by Seeding or Sodding.

END OF SECTION

SECTION 336020

STANDARD LIFT STATIONS

PART 1 - GENERAL

1.1 SCOPE

- A. This specification provides the requirements for design and installation of wastewater pumping stations.

1.2 GENERAL

- A. The following specification is intended for use for the design, selection of materials and construction of a standard submersible wastewater pump lift station and all appurtenances. Design and construction shall comply with the applicable design and installation requirements as established by the Florida Department of Environmental Protection (FDEP), Florida Administrative Code (FAC), and the most recent edition of "Recommended Standards for Wastewater Facilities (Ten States Standards)", as applicable. The lift station shall meet the requirements of the FDEP Permit if applicable. The specifications herein state the minimum requirements of City of North Port Utilities (NPU).

A permanent by-pass pump, Telemetry Control Unit (TCU), above ground valves, are items that are part of all standard lift stations. The standard lift station has optional capabilities such as an odor control system and Variable Frequency Drives (VFDs).

- B. GENERAL SPECIFICATIONS: Units described shall be new, unused, and of the current year's production.
- C. WORK INCLUDED: The Contractor shall, unless specified otherwise, furnish all labor, materials, equipment, tools and all other associated appurtenances, necessary to do the work required under the contract to include but not limited to unloading, hauling, and distributing all pipe, fittings, valves and appurtenances. The Contractor shall also remove any surfacing as required; excavate the trenches and pits to the required dimensions; construct and maintain all required traffic control; sheet, brace, and support the adjoining ground or structures where necessary; handle all drainage or ground water; provide barricades, guards, and warning lights; lay and test the pipe, valves, fittings and appurtenances; backfill and consolidate the trenches and pits; maintain all surfaces over the trench until surface restoration is completed; restore the surfaces

unless otherwise stipulated; remove surplus excavated material; and clean the site of the work. The Contractor shall also furnish all labor, materials, equipment, tools and all other associated appurtenances required to rearrange sewers, conduits, ducts, pipes, or other structures encountered in the installation of the work.

- D. LOCATION OF THE WORK: The location of the work is as shown in the Contract Documents. The accessibility to the work sites shall vary, as the lift station may be located in landscape areas, utility easements, residential and/or commercial backyards, and various other locations. Damage to existing pavement surfaces, base courses and/or other surface improvements as a result of the Contractor's activities shall be restored to like-new condition by the Contractor as provided for in the contract bid documents. The Contractor shall implement all required measures to provide NPU personnel and equipment with complete access to all work site areas during the entire course of performing this project.
- E. COORDINATION OF THE WORK: The Contractor shall be responsible for the satisfactory coordination of the construction of the force mains with other construction and activities in the area. Delays in work resulting from lack of such harmony shall not in any way be a cause for extra compensation by any of the parties.
- F. RESPONSIBILITIES
1. Notice to Residents: The Contractor shall coordinate with NPU and the Contractor shall be responsible for notifying affected residents by the means of door hangers, mailings and/or all other appropriate means to alert residents at various times of the different phases of the construction of the standard lift station. The notifications shall indicate the various work activities that the Contractor will be performing on their street and what they can expect as far as service outages, disruption of traffic, access inconvenience, unusual odors and other activities affecting residents.
 2. Licenses and Permits: The Contractor shall be responsible for obtaining all licenses, permits, authorizations, approvals, access agreements, consent from utilities/persons/organizations upon whose property is impacted, written releases of responsibility and all other required documents.
 3. Work Access: The access to the site is shown on the contract documents. Additional accessibility to the site, as deemed necessary by the Contractor beyond what is shown on the construction plans, shall be the responsibility of the Contractor, and all expenses associated with work site additional accessibility shall be taken into consideration as part

of the Contractor's bid unit prices. Written releases from the property owner impacted by additional accessibility obtained by the Contractor shall be provided to NPU.

4. Clearance of Blockages or Obstructions in the Sanitary Sewer System: The Contractor shall be responsible for clearance of blockages or obstructions in the sanitary sewer system created by the Contractor's construction methods.
5. Location and Exposure of Manholes: The Contractor shall expose only those sanitary sewer structures necessary to perform the work as shown on the engineering drawings.
6. Existing Utility Operations: NPU shall shut down or manually operate all existing potable water, reclaimed water and sanitary sewer systems necessary for performance of the work. The Contractor shall submit a request to NPU for shut down or operational changes a minimum of 72 hours in advance.
7. By-Pass Operations: The Contractor shall be responsible for continuous maintenance of flow of all existing utilities at the project site, unless otherwise agreed to by NPU. By-Pass Operations shall include furnishing and installing bypass pump including float control and high level alarm capable of notifying the Contractor and/or NPU, temporary piping and fitting connections, fueling all pumping equipment and daily checks of pumps, fuel levels and all other components of the bypass operation.
8. Water Access: The Contractor shall be responsible for obtaining water access necessary for performance of work under the contract from designated fire hydrants at the site of work, a construction meter, or other suitable designated sources.
9. Disposal: The Contractor shall clean up and dispose of all waste materials from the construction activities including all materials removed from the sanitary sewer system in conformance with all laws, regulations and standard practices.
10. Secure Storage Area: The Contractor shall find secure storage areas of a size adequate to accommodate the required vehicles, equipment and materials for the period of performance of the contract. NPU may provide space at its plant site, as available to store materials. If adequate space is not available at NPU's plant site it is the Contractor's responsibility to secure adequate secure storage areas.
11. Maintenance of Traffic: The Contractor shall be responsible for all maintenance of traffic and obtaining approval of a Maintenance of Traffic (MOT) Plan from the City of North Port Public Works Department for work within the right-of-way of any City road and/or from the Florida Department of Transportation (FDOT) for work within the right-of-way of any State Road.

G. **WORKING HOURS:** The work shall be carried out in accordance with local ordinance and not to cause any unreasonable nuisance to affected residents and in accordance with contract and bid documents. Under emergency conditions, this limitation may be waived by the consent of the NPU.

1.3 **METHOD OF MEASUREMENT AND PAYMENT**

The work shall be measured, and the compensation determined in the following manner including all labor, materials, equipment, installation, testing, startup, painting, training technical support, operation and the maintenance manuals and appurtenances necessary to complete all the work in accordance with the contract documents.

A. **SITE WORK:** This item includes the satisfactory coordination of utility construction, project site clearing and grubbing, fence removal and restoration, removal and disposal of existing bituminous and/or concrete materials, existing structures, existing culvert or other pipe, furnishing and installing fill material, all necessary grading of the site and all other associated work required to complete the project in accordance with the contract documents and shall be measured and paid for on a lump sum basis unless otherwise provided in the bid form.

B. **WET WELL, ACCESS HATCH AND CONCRETE COVER AND SLAB:** Wet well, access hatch and concrete cover and slab including excavation, dewatering, base materials, backfilling, external and internal coatings, provisions for pipe openings, joint sealing and wrapping, exfiltration testing of the wet well, and all other associated work required to complete the project in accordance with the contract documents shall be measured and paid for on a lump sum basis unless otherwise provided in the bid form. To avoid flooding, both the wet well top and concrete slab under the above ground piping shall be graded such that they are a minimum of six inches (6") higher than the surrounding grades. The concrete slab under the above ground piping shall be included in this bid item and no separate bid item shall be provided.

C. **SUBMERISBLE SEWAGE PUMPS:** Submersible sewage pumps including associated hardware, cables, guide rails, support brackets, chains, all electrical wiring to the Control Panel, conduits and all other associated appurtenances required to complete the project in accordance with the contract documents shall be measured and paid for on a per each basis per each submersible sewage pump size specified.

D. **MAIN POWER AND ELECTRICAL SERVICES:** Main power electrical services including wiring and conduit from the service point in the Florida Power and Light (FPL) installed hand hole to the FPL meter can, wiring and conduit from the FPL meter can to the standard lift station control panel, the main power disconnect in the panel, and all other associated

appurtenances required to complete the project in accordance with the contract documents shall be measured and paid for on a lump sum basis.

- E. PIPING AND VALVES: Piping and valves, located within the fenced in area limits of the standard lift station site, including fittings, flexible couplings, flange adaptors, flange connectors, gauges, pipe supports, brackets, vents, and all other associated appurtenances required to complete the project in accordance with the contract documents shall be measured and paid for on a lump sum basis.

All piping and appurtenances outside the fenced in area limits of the standard lift station site shall be measured and paid for within other bid items as provided in the bid form.

- F. CONTROL PANEL: Control panel including the following general components: wet well liquid level transmitter, electrical wiring and connectors, supports, switches, sensors, controllers, alarms, indicator lights, meters, electrical equipment, enclosure, panels, controls, indicators, waterproof connectors (DRYCONN Waterproof Connectors, or approved equal), posts, motor starters, main circuit breaker, operating handles, magnetic contactor coils, seal leak probe, permanent labels, alternator relay, fused control circuit transformer, adjustable three phase power monitor, wiring diagram, grounding rods, explosion proof fittings, surge protector equipment, suppressors fittings, brackets, conduits, and all other associated appurtenances required to complete the project in accordance with the contract documents shall be measured and paid for on a lump sum basis.

- G. WATER SERVICE: The water service including tap, piping, meter box assembly, backflow prevention device, spigot, hardware, fittings, brackets, supports and all other associated appurtenances required to complete the project in accordance with the contract documents shall be measured and paid for on a lump sum basis.

- H. DRIVEWAYS: The driveways including removal of existing concrete/bituminous and aggregate base sections, saw cutting of existing concrete/bituminous edges, preparation of subgrade, placement of aggregate base, construction of concrete/bituminous surfacing and all other associated appurtenances required to complete the project in accordance with the contract documents shall be measured and paid for on a square yard basis.

- I. CULVERTS: The culvert pipe, end sections, base material and all other associated appurtenances if applicable and required to complete the project in accordance with the contract documents shall be measured and paid for on a per linear foot basis per each size specified.

- J. FENCE AND GATES: The fence and gates including posts, pipes, fabric, bars and straps, fasteners, gate latches, coating, pig ring ties, hardware and accessories, concrete footings and all other associated appurtenances required to complete the project in accordance with the contract documents shall be measured and paid for on a lump sum basis.
- K. FLOOD LIGHT: A weather-proof 300 W LED flood light, suitable for mounting to TCU antenna tower or other structure as provided on the engineering drawings including posts, conduits, wiring, panel switch, hardware and accessories, concrete footings and all other associated appurtenances required to complete the project in accordance with the contract documents shall be measured and paid for on a lump sum basis.
- L. TELEMETRY CONTROL UNIT (TCU) – The Telemetry Control Unit including concrete base, tower, enclosure, galvanized steel piping, tie wraps, antenna, coaxial cables, conduits, ground rod, default screen or indicating LED, site signal survey and all other associated appurtenances required to complete the project in accordance with the contract documents shall be measured and paid for on a lump sum basis.
- M. STATIONARY BY-PASS PUMP - A diesel stationary by-pass pump (see Specification 336022 for more information) and Telemetry Control Unit (TCU) are equipment to be included for each standard lift station and included in the contract documents. These items shall be measured and paid for as separate bid items as provided in the bid proposal.
- A sound attenuated; compressor-assisted horizontal sewage pump driven by a water-cooled diesel engine. The pump shall be fully automatic, self-priming from dry conditions and capable of handling large volumes of air, water, and solids. The pump shall be manufactured by Thompson Pump & Manufacturing Company. The stationary by-pass pump includes diesel engine, pump, priming system, mounting frame, sound enclosure, pump control panel, solar battery charger, inside work lights and all items in the separate specification number 336022.
- N. VFD (OPTIONAL) – VFD is optional equipment for each standard lift station and if required in the contract documents shall be measured and paid for as separate bid items as provided in the bid proposal. The VFD including the wiring, separate panel, control logic, controller, input circuit breaker, harmonic suppression equipment, contactors, reactors, controls, conduits, connectors and all other associated appurtenances required to complete the project in accordance with the contract documents shall be measured and paid for on a lump sum basis.
- O. ODOR CONTROL SYSTEM (OPTIONAL) –Odor control is optional equipment for each standard lift station and if required in the contract

documents shall be measured and paid for as separate bid items as provided in the bid proposal. The odor control system (biofilter unit only, biofilter unit with optional secondary activated carbon polishing unit or stand-alone activated carbon filter unit) including motors, enclosure, skids, wiring, valves, media, absorption material, absorber system, absorber vessel, VFD controlled centrifugal fan with sound attenuation enclosure, switches, control transformer, gauges, sample probes, screen, grates, ductwork, conduits, and connectors, piping, concrete pad, anchors all other associated appurtenances required to complete the project in accordance with the contract documents shall be measured and paid for on a lump sum basis.

P. MISCELLANEOUS

All items required for the completion of the standard lift station and not included as a specific bid item shall be considered incidental to the project and no direct compensation will be made therefore.

1.4 REFERENCED STANDARDS (LATEST REVISION)

AWWA: C-153, C-900, C-905, C-909, C-906-90, C-151, C-153, C-111, C-600, C-651, C-652 and C-913

ASTM: A-139, D-883, D-1785, D-1869, D-1120, D-2241, D-3350, D-1248-68, D-1598, D-1599 , D-2583, D-2563, D-4097-82

PS 15-69: National Bureau of standards Voluntary Product Standard "Custom contact molded Reinforced Polyester Chemical Resistant Process Equipment".

ASME: PTC 8.2

FDEP: Wastewater Collection/Transmission System Requirements

AASHTO Code

Florida Administrative Code (FAC)

Ten States Recommended Standards for Wastewater

National Electrical Code (NEC)

NEMA

Underwriters Laboratories (UL)

Federal Communication Commission (FCC)

Institute of Electrical and Electronics Engineers (IEEE)

Internal Corrosion Direct Assessment (ICDA)

National Fire Protection Association (NFPA)

National Bureau of Standards (NBS)

Air Movement and Control Association (AMCA)

1.5 SUBMITTALS

The Contractor shall submit in writing, documentation to justify approval of these materials by NPU prior to the start of the project.

No fabrication shall take place until the final shop drawings are reviewed by NPU. Final approval is at the discretion of NPU.

A. SHOP DRAWINGS

1. **STRUCTURE(S):** The Contractor shall provide shop drawings for the structure(s) certified by the manufacturer. The submittals shall include the specifics being proposed for the outside coatings, inside coatings of the wet well, top concrete elevations and reinforcement, access hatch, structural loading, buoyance provisions, outside seam wrap, sealant between structure sections, invert and clocking of piping, size and location of openings, water proof gaskets and any other appurtenances applicable to the structure(s).
2. **SUBMERSIBLE SEWAGE PUMPS:** The Contractor shall provide shop drawings for the submersible sewage pumps certified by the manufacturer. The submittals shall include at a minimum: pump characteristic curves showing capacity in GPM, NPSH, TDH, efficiency, pumping horsepower from 0 to 110 percent of design capacity, impeller type, discharge diameter, passible sphere size, design drawings, a written description of the interchangeability of rails and discharge between the supplied submersible sewage pump, and any other appurtenances applicable to the submersible sewage pumps. The shop drawings shall include certification data in the form of testing results indicating that all state, federal, and engineering standards are met. If requested by NPU, the Contractor shall provide certified factory pump performance test data in the form of Section 6 of ASME PTC 8.2.
3. **CONTROL PANEL:** The Contractor shall provide shop drawings for the control panel. The shop drawings shall include schematics, manufacturer brochures, and test results for pump settings, all panel components, all other electrical components and appurtenances

applicable to the control panel. The shop drawings shall include certification data in the form of testing results indicating that all NEMA, UL, state, federal, and engineering standards are met.

4. STATIONARY BY-PASS PUMPS: Refer to the separate Stationary Bypass Pump Specification 336022.
5. TELEMETRY CONTROL UNIT (TCU): The Contractor shall provide shop drawings for the TCU. The shop drawings shall include schematics, manufacturer brochures, and test results for pump settings, flood light, antenna, tower, all other TCU components and appurtenances applicable to the TCU. The shop drawings shall include certification data in the form of testing results indicating that the contract requirements and all NEMA, UL, state, federal, and engineering standards are met.
6. ODOR CONTROL (OPTIONAL)

a. General:

The odor control system shall be supplied by a manufacturer who has been regularly engaged in the design and manufacture of the equipment having a minimum of five (5) years' experience in its design, fabrication, and testing of odor control systems of the type specified. The equipment supplier shall provide a list of a minimum of ten (10) identical installations of the type specified that have been in operation for a minimum of five (5) years. Other manufacturers shall demonstrate to NPU its equipment is of equal quality of the manufacturer specifically named herein.

The Contractor shall submit complete shop drawings for the odor control system, together with all piping, ductwork, valves, and control for review by NPU. The shop drawings shall include schematics, manufacturer brochures, and test results for all odor control components and appurtenances applicable to the proposed odor control. The shop drawings shall include certification data in the form of testing results indicating that the contract requirements and all NEMA, UL, and engineering standards are met.

The Contractor shall complete the "TBDs" in table "A" below for the odor control system being proposed based on the size of the wetwell, influent flows, inlet, outlet, standard lift station operational temperatures and the estimated inlet hydrogen sulfide (H₂S) concentration in parts per million (ppm). The design documents shall be provided by the manufacturer to NPU certifying that the odor control system meets the contract requirements.

Table A

Air Flow Rate, cfm	TBD
--------------------	-----

Estimated Inlet H2S Concentration, ppm	TBD
--	-----

The Contractor shall submit the following information for review before the equipment is fabricated:

- 1) Letters of Certification of Compliance of materials, equipment, etc.
 - 2) Final certified drawings showing outline dimensions, foundation layout or mounting information, and other pertinent dimensions.
 - 3) Field assembly drawings and/or diagrams.
 - 4) Schematic and wiring diagrams of power, control, and piping systems with all devices, waterproof connectors (DRYCONN waterproof connectors, or approved equal), and wires uniquely numbered and clearly indicating between factory and field wiring. All field wiring shall be included for each diagram to describe all modes of operation of the system indicated. Where the integrated system requires interlocking and control and other components in normal operation, these components shall be included in the description of operation.
 - 5) Drawings of system showing assemblies, arrangements, piping, electrical, mounting details, equipment outline dimensions, fitting size and location, motor data, operating weights of all equipment and sufficient information to allow NPU to check clearances, connections, and conformance with the specifications.
 - 6) Renewal parts list with diagrammatic or cross-section drawing showing part identification. Material analysis or trades designation for each significant part shall be noted on parts lists or on a separate sheet.
 - 7) Materials of construction of all equipment.
 - 8) Control panel drawings shall indicate all equipment installed inside and outside of the panel including the location of all alarms (for biofilter); lamps; complete instrumentation; and control, logic and power wiring diagrams.
 - 9) Electrical equipment rating and data sheets for all devices.
 - 10) Design calculations certified by a Registered Professional Engineer with demonstrated experience in the design of these systems.
 - 11) Pump data and performance curves showing flow, pressure, and horsepower (for biofilter).
 - 12) Specifications, performance data, and calibration curves for exhaust fan and auxiliary components
- b. Biofilter:
Any manufacturer whose main business is Fiberglass Reinforced Plastic (FRP) manufacturing shall not be accepted as a supplier of the complete system.
- c. Activated Carbon Adsorber:
Any manufacturer whose main business is high density polyethylene (HDPE) manufacturing shall not be accepted as a

supplier of the complete system.

7. VFD (OPTIONAL): The Contractor shall provide documentation with the material submittals on the experience of the VFD manufacturer and their interfacing with the submersible pump manufacturer.

The Contractor shall also submit a manufacturer's statement that the VFD meets the requirements of Federal Communication Commission (FCC) and Institute of Electrical and Electronics Engineers (IEEE). Adequate IC (inductance-capacitor) filters shall be provided as required to meet these criteria.

PART 2 - PRODUCTS

2.1 GENERAL

All equipment and products shall be permanently identified with the model number and manufacturer's nomenclature.

2.2 EQUIPMENT

The equipment used in this work shall be all new and conform to the requirements for class, kind, size and material as specified below and/or as provided in other sections of the contract documents.

A. SUBMERSIBLE SEWAGE PUMPS:

1. GENERAL

- a. The submersible sewage pumps covered by this specification are intended to be standard pumping equipment of proven ability as manufactured by Flygt Pumps.
- b. The submersible sewage pumps shall be designed, constructed and installed in accordance with the best practices and methods and shall operate satisfactorily when installed as shown on the engineering drawings and/or standard details.
- c. The submersible sewage pumps shall be heavy duty electric submersible, centrifugal non-clog units designed for handling raw and unscreened wastewater (minimum of three (3") inch sphere). The submersible sewage pumps shall be capable of operating in a liquid temperature up to 115°F and to a depth of 65 feet.
- d. The submersible sewage pump and motor unit shall be suitable for continuous operation at full data plate load while the motor is completely submerged, partially submerged or totally non-submerged. The use of shower systems, secondary submersible sewage pumps or cooling fans to cool the motor shall not be acceptable. The submersible sewage pumps mechanical seals and

motor units shall be from the same manufacturer to achieve standardization of operation, maintenance, spare parts, manufacturer's service, and warranty.

- e. The submersible sewage pump shall be tested and approved by Factory Mutual or U.L. as explosion proof for use in Class I, Groups C and D, Division 1 hazardous locations.
- f. The submersible sewage pump shall have a sliding bracket for connecting to the dual guide stainless steel rail system.
- g. The submersible sewage pump shall have a manufactured sized electrical cable and shall be a minimum of 50 linear feet. The cable shall conform to NEC and ICDA Standards with P-MSHA approval. The cable shall be sealed with a protective covering prior to installation.
- h. The submersible sewage pump shall include a 316 stainless steel chain capable of supporting the weight of the submersible sewage pump for installation and removal of the submersible sewage pump. The chain shall be connected to the submersible sewage pump bail using a 316 stainless steel clevis. The length of the chain shall be equivalent to the depth of the wet well plus additional six (6') feet.
- i. The submersible sewage pump discharge diameter shall be as specified on the engineering drawings and/or NPU standard details.
- j. The submersible sewage pump shall be cast iron with appropriate coating to protect submersible sewage pump from corrosive properties of wastewater.
- k. The impeller shall be mounted directly on the motor shaft extension in such a manner that it shall not become detached if the submersible sewage pump is operated in the wrong direction. The impeller shaft shall be 420 stainless steel or greater and shall extend from the motor to the impeller cap nut.
- l. All submersible sewage pump mated surfaces shall be machine fitted for watertight sealing.
- m. A 316 stainless steel lifting bail handle shall be provided on the submersible sewage pump housing suitable for lifting the entire submersible sewage pump assembly and attaching the lift chain.
- n. The submersible sewage pump shall operate to a maximum submergence of 65 feet including electrical cable entry.
- o. All electrical parts shall be housed in an air or oil filled cast iron, water-tight casing.
- p. All external hardware shall be 316 stainless steel.
- q. The motor shall be designed to allow a minimum of 15 starts per hour.
- r. The motors shall include thermal and moisture protection to shut down the motor due to high operational temperatures or infiltration of moisture. The motor shall be automatic restarted once the operational temperature is achieved.
- s. All other components and appurtenances shall be as specified on the engineering drawings and in the NPU standard details.

2. APPROVED PRODUCTS: Flygt is the submersible sewage pump manufacturer approved by NPU.

B. CONTROL PANEL

1. GENERAL

The submersible sewage pump motor control elements shall be installed in a 316 stainless steel NEMA 4X enclosure and include the following equipment:

- a. The panel shall be constructed of a heavy-duty box frame of all welded construction, utilizing specially formed #12-gauge 316 stainless steel angle and channel members.
- b. The dead front interior panel(s) for instrument mounting shall be constructed of a minimum of #11-gauge aluminum.
- c. The interior panel(s) for instrument mounting shall be constructed of a minimum of #14 gauge epoxy coated steel.
- d. Panel mounted controls and indicators shall maintain panel integrity. Suitable stiffness shall be provided when required to maintain flatness and provide extra rigidity.
- e. All panels wiring to external equipment shall be terminated with waterproof connectors (DRYCONN waterproof connectors or approved equal).
- f. All waterproof connectors (DRYCONN waterproof connectors or approved equal) shall be marked with legible permanent labels or otherwise identified.
- g. The panel shall be mounted on four (4") inch tubular top capped aluminum posts installed in concrete above the 100-year flood plain in accordance with the engineering drawings and standard details.
- h. All circuit breakers shall be accessible without opening the control panel dead front door(s).
- i. The panel shall include at a minimum the following for each submersible sewage pump: a motor starter, a Hand/Off/Auto (HOA) switch, a circuit breaker mounted with the operating handles through the dead front door(s), a leak seal indicating light, and an elapsed time meter.
- j. The panel shall contain a manual pump control operated by a manual HOA by-pass switch located in the main panel which is NOT an automatic redundant switch.
- k. The panel shall include at a minimum: a wet well level transmitter control circuit, 120-volt AC audio and visual alarms, an emergency generator receptacle with circuit breaker, a main circuit breaker, a control circuit breaker, and a 12-volt DC audio and visual battery backup alarm system.

- l. All power shall be disconnected from the control elements when the standard lift station main disconnect is in the "OFF" position.
- m. In each motor, a heat sensor thermistor and a seal leak probe shall be wired to a red warning signal light on the dead front door and shall be marked with legible permanent labels.
- n. An alternator relay shall be supplied to alternate the individual submersible sewage pump on each successive cycle.
- o. A fused wet well liquid level sensors control circuit transformer shall be supplied to operate controls.
- p. In 480-volt AC applications, a fused control circuit transformer shall be supplied to provide 120-volts AC auxiliary equipment power.
- q. An adjustable single or three phase power monitor shall be provided to indicate and protect the pump via the control circuit in the event of loss of any phase, low and high voltage on any or all phases, and phase reversal with automatic reset and built-in time delay on trip.
- r. Audio and visual alarms shall be installed for monitoring high water levels, system equipment failures, and main input power level failures. Audio and visual alarms shall be wired to sensors provided for a high-water levels. Water level and system equipment failure alarms shall be powered directly from the main power supply to the panel. The audio alarm shall be disabled by a manual silence switch; however, the visual alarm shall remain on until the alarm condition is corrected. If the alarm is a result of a loss of power to the standard lift station, the alarms shall automatically reset with the restoration of land line power or from a portable generator set. The loss of power audio and visual alarms shall be connected to a continually charged 24-hour back-up 12- volt battery.
- s. The panels shall be wired and assembled per UL 508 Standards. All electrical components and materials shall be listed by UL and shall bear the appropriate UL listing mark or classification. Each panel shall be listed and labeled as UL 508, Industrial Control Panels shall comply with NFPA 79 - Industrial Machinery. A permanent, non-paper wiring diagram shall be mounted on the inside of the cabinet door.
- t. A 120 VAC time delay relay (0 to 60 second adjustable on delay) to re-energize control circuit of lag submersible sewage pump after power restoration shall be provided for step loading on submersible sewage pumps over 20 HP. VFDs shall be provided for submersible sewage pumps over 20 HP as approved by NPU.
- u. All control panels shall include a grounding rod with 10-gauge wire that is installed in accordance with current local, state and national codes.
- v. 316 Stainless steel and schedule 80 polyvinyl chloride conduit piping shall be provided and installed as shown on the NPU design detail for connections between the control panel and the wet well structure, the control panel and the TCU, the panel and the stationary diesel

by-pass pump, the panel and the odor control (if required), the panel and the ground rod, and the panel and the FPL service point. Explosion proof fittings shall be provided and installed on the conduit as shown on the NPU design detail for connections between the control panel and the wet well structure.

- w. A trouble light including switches shall be mounted in the control panel.
- x. Surge protector equipment in accordance with UL 1449 Standards shall be installed on the load side of the control panel main circuit breaker for protection of all AC electrical equipment in the panel and the motors from the effects of lightning induced currents, substation switching transients, and internally generated transients.
- y. All other components and appurtenances shall be as specified on the engineering drawings and in the NPU standard details.

2. APPROVED PRODUCTS

All electrical and accessories shall meet NPU standard details and specifications and shall be reviewed by NPU with the standard lift station submittals except as noted below.

- Trouble Light: Leviton 9880
- 120 Volt Alarm Light: Ingram LXR-40 or Ohio Electric RL-3K
- 120 Volt Alarm Horn: Edwards ALA-896-N5
- 12 Volt Alarm Light: Ingram SLR-123
- 12 Volt Alarm Horn: Ingram AH-122DG
- Elapsed Time Meter: ETMAC 200-10NG7 Round Mount
- Surge Suppressor: Current Technology Transguard 150

C. WET WELL LIQUID LEVEL TRANSMITTER

1. GENERAL:

- a. The wet well liquid level transmitter shall be a continuous level measurement, radar transmitter.

1. APPROVED PRODUCTS:

All wet well continuous level measurement radar transmitters and accessories shall meet NPU standard details and specifications.

The following transmitter and controller are approved:

- Vega VEGAPULS C 21
- Vega VEGAMET 861

D. TELEMETRY CONTROL UNIT (TCU)

1. GENERAL

- a. The TCU transmits analog signals from the lift station to the NPU central monitoring location and from the NPU central monitoring location to the lift station.
- b. The TCU includes a grounding rod with 10-gauge wire and shall be installed in accordance with current local, state and national codes.
- c. The TCU data shall be displayed continuously at the TCU by a default screen and indicating LED and shall indicate, at a minimum:
 - 1) Operating status of each submersible sewage pump
 - 2) Operating mode of the standard lift station
 - 3) Wet well liquid level sensors status
- d. All other components and appurtenances including tower, antenna, control box, conduits, etc. shall be as specified on the engineering drawings and in the NPU standard details.
- e. NPU will provide the TCU frequency to the contractor.

2. APPROVED PRODUCTS

The TCU and accessories shall meet NPU standard details and specifications as determined by NPU.

The following TCU manufacturer is approved:

- Data Flow Systems, Inc.

E. STATIONARY BY-PASS PUMP

See separate City of North Port Specification number 336022.

F. VFD – OPTIONAL ITEM

1. GENERAL

- a. A dedicated VFD for each submersible sewage pump and connecting wiring shall be supplied by the submersible sewage pump manufacturer for all pumps 20 hp and higher. The VFDs shall be installed inside the Control Panel box, if required. Supplementary cooling in the form of an air conditioning unit shall be used, if required by NPU.
- b. The VFD shall consist of a variable frequency controller, input circuit breaker, harmonic suppression equipment, output isolation contactor, input and output line reactors, and controls. All of the components shall be a complete unit, factory wired, and tested as a complete system. Each VFD shall operate as a stand-alone unit with no interaction with the other VFD.

- c. The VFD shall maintain a .95 minimum true power factor though out the entire speed range and shall be used with any standard NEMA-B squirrel-cage induction motor having a 1.15 service factor.

G. ODOR CONTROL – OPTIONAL

1. GENERAL

- a. The odor control system shall be a primary biofilter unit including a built-in carbon filter stage and, if required, an optional secondary activated carbon polishing unit connected to the biofilter unit; a VFD controlled centrifugal fan installed in a sound attenuation enclosure; interconnecting ductwork; electrical wiring and conduit; and appurtenances for a complete operating system.
- b. The odor control system shall treat in a single pass odorous air from the wet well. The system shall be designed for manual and continuous automatic operation. Access manways shall be provided to allow access to the internals of the system. The system shall be designed to withstand a temperature up to 120 degrees F. The module and all accessories shall be factory mounted, piped, and wired to the maximum extent possible. The system shall be installed on the lift station pad with stainless steel fasteners.
- c. The odor control system shall be skid mounted and designed to maintain proper alignment of the installed unit on a concrete pad as detailed on the engineering drawings using properly sized epoxy HILTI anchors. The controls shall be attached to the skid assembly and shall be housed in a waterproof NEMA 4X enclosure.
- d. The overall system size, including the fan, controls, and appurtenances shall not exceed the dimensions shown on the engineering drawings. At a minimum, access manways shall be provided between the treatment stages. A portion of the system top shall be removable for access to the top of the second stage.
- e. The odor control system shall meet the following performance when operating:

INLET	OUTLET
1-10 ppm H ₂ S	0.1 ppm H ₂ S
Greater than 10 ppm H ₂ S	1.0% of inlet (99.0% removal)

2. BIOFILTER

- a. The biofilter odor control unit shall be a two-stage, biological absorption/adsorption system that shall include but not be limited to a fiberglass reinforced plastic (FRP) vessel, nozzles, two independent stages of inorganic treatment media (biological and built-in carbon polishing), moisture controls, nutrient supply system, VFD controlled air supply fan, ductwork, dampers, and all necessary

accessories. The biological treatment stage shall utilize a granular inorganic media to facilitate absorption and adsorption of odor compounds designed to remove minimum of 99% of H₂S vapor in a single pass. The polishing stage shall utilize a granular media designed to adsorb odorous compounds with the ability to support biological degradation of the compounds. The first stage shall operate from an independent water distribution system to irrigate the top of the first media bed with complete and even coverage via spray nozzles to maintain optimum wetted conditions to support unique microbial growth for biological destruction of the odorous compounds and removal of toxic metabolites. Biofilter odor control units using any type of organic media and biofilter odor control units using a single inorganic media shall not be acceptable. The complete treatment vessel shall be fabricated of premium grade FRP.

- 1) The air enters the vessel through the humidification section. After humidification, the first treatment stage contains media specifically designed to support biological growth for degradation of odor compounds. This stage absorbs odors from the air stream. The second polishing stage contains media specifically designed to adsorb odor compounds and to support biological degradation of those compounds. This stage provides final removal of odors to the specified level. Overall media depth shall be a minimum of 48 inches.
- 2) The first stage of media shall be wetted with fresh potable or re-use make-up water.
 - b. The system shall include all piping, valves, control panel and internals pre-mounted and piped on the unitary constructed system. The material of construction of internals shall be as follows:

Packing Media Support	HDPE and FRP
Liquid Distributor	PVC
Spray Nozzles	PVC
Humidifier Nozzles	316 SS

- c. The multi-stage packaged FRP unit shall be of unitary construction. The system shall be shipped as a single piece.
- d. Design and Performance Criteria:
 - 1) Criteria: The biofilter odor control unit shall be capable of removing foul air at a rate no lower than the rate shown on the following table.

INLET	OUTLET
1-10 ppm H ₂ S	0.1 ppm H ₂ S
Greater than 10 ppm H ₂ S	1.0% of inlet

- 2) System Performance: The biofilter odor control unit shall demonstrate the following performance when operating under design flow conditions listed above:

Maximum Pressure Drop: The pressure drop across the odor control unit shall not exceed 5.0 in. w.c. at the maximum air flow rate specified above.

e. Miscellaneous Material of Construction

- 1) The vessel and accessories shall be contact molded manufactured in accordance with NBS PS 15-69, ASTM D 4097 for contact molding. Any material of construction other than FRP with premium grade resin will not be allowed.
- 2) Resin used in the system liner shall be a premium vinyl ester type such as Hetron 922 by Ashland Chemicals, Derakane 411 by Dow Chemical, Vipel F010 by AOC, or NPU approved equal. The resin shall be reinforced with an inner veil of a suitable synthetic organic fiber such as Nexus 111-00010.
- 3) Glass fiber reinforcement used shall be commercial grade corrosion resistance borosilicate glass. All glass fiber reinforcement shall be Type C, chemical grade, Type E electrical grade. Surfacing veil shall be 10 mil Nexus 111-00010 or equal. Mat shall be Type "E" (electrical grade) glass, 1 1/2 oz. per sq. ft with a nominal fiber length of 1.25 + 0.25 inches, with a silane finish and styrene soluble binder. Continuous glass roving, used in chopper gun spray-up applications shall be type "E" grade with chrome or silane coupling agent. Alternate layers of mat and woven roving shall be used for reinforcement.
- 4) Unless otherwise specified, all fasteners, and metal attachments such as anchors, brackets etc. shall be ANSI 316 SS. Unless otherwise specified, all gaskets shall be EPDM.

f. Fabrication:

- 1) Fabrication shall be in accordance with NBS PS 15-69, ASTM D 3299, and ASTM D4097. All non-molded surfaces shall be resin incorporating paraffin coated to facilitate a full cure of the surface. All cut edges, bolt holes, and secondary bonds shall be sealed with a resin coat prior to the final resin paraffin resin coat. All voids shall be filled with a resin paste.
- 2) The inner surface of all laminates shall be resin rich and reinforced with one layer of NEXUS 111-00010 with a minimum thickness of 10 mils. The interior corrosion liner shall consist of two layers of one and one half (1-1/2) oz. per sq. ft. chopped strand mat. If the application is by chopper gun, the spray upglass fiber shall be one half (1/2") in. to two (2") in. long. The total corrosion liner thickness shall be a minimum of 100 mils and have a resin to glass ratio of 80/20. All edges of reinforcement to be lapped a minimum of one (1)

- inch.
- 3) Structural laminates shall consist of alternating layers of one and one half (1-1/2) oz. per sq. ft. mat or chopped glass and 24 oz. per sq. yard woven roving applied to reach the designed thickness. The exterior surface shall be relatively smooth and shall have no exposed glass fibers. The exterior shall be surface coated with gel coat containing ultraviolet light inhibitors.
 - 4) Accessories: Air inlet, air outlet, spray headers, baffles, media support, drain, and all connections shall be provided by the manufacturer. Tie down lugs shall be integrally molded into the walls of the vessel. All external bolts shall be 316 SS and designed for the specified loads. Interior fasteners shall be of corrosion resistant materials such as PVC or FRP.
 - g. Neoprene Pad: A one quarter (1/4") inch thick, 60 durometer neoprene rubber sheet shall be placed underneath the vessel before installation on lift station pad.
 - h. Exhaust Fan
 - 1) The exhaust fan shall be centrifugal design manufactured of FRP with a statically and dynamically balanced radial blade wheel. The fan inlet shall be slip type, and the fan outlet shall have a flanged nozzle. The fan shall have a neoprene shaft seal.
 - 2) Fan shall be supplied with a TEFC motor with 1.15 service factor suitable for three phase, 60 Hz, 480-volt service and rated for Class 1, Div. 2, Group D installation. The fan shall be direct driven. The motor shall be inverter-duty and controlled by a VFD.
 - 3) The fan shall be tested and rated in accordance with AMCA and bear the AMCA seal.
 - i. One of the two mineral vessels shall be fitted with a top-mounted, five-cycle multiport control valve to operate the backwash, brining, slow rinse, fast rinse, and refill cycles. An additional piston assembly shall be included to control the duty/standby status of the two vessels. A brass control valve including fixed and self-adjusting flow regulators shall be provided. A hydraulically balanced Teflon coated piston shall be provided to perform the cycles of regeneration.
 - j. Instrumentation and System Controls
 - 1) The electrical control panel shall provide electrical control for the exhaust fan and water addition system. A 3-phase power supply shall be supplied to the panel to power the system.
 - 2) The control panel enclosure shall be rated NEMA 4X. The panel shall be remote mounted by the contractor next to the system assembly at least three (3') feet away to comply with requirements of a Class 1, Division 2, and Group D installation. The Contractor shall install and wire the local control panel to the biofilter mounted fan, metering pump, and solenoid valve. The control panel shall be factory tested to full operation with all other components prior to shipment.

- 3) The panel shall have the following components or capabilities:
 - Fan switch (ON-OFF).
 - Push-to-test button for water valve.
 - Timer relay for on/off control of water valve.
 - Blower VFD
 - Nutrient Pump (ON-OFF-AUTO)
- 4) The water control cabinet shall be constructed from a NEMA 12 rated FRP cabinet with all internal piping SCH 80 PVC. The cabinet shall be mounted to the system assembly. The cabinet shall contain the following components:
 - Pressure reducing valve
 - Nutrient Pump (rated for installation in a Class 1, Division 2, Group D area)
 - Irrigation solenoid valve (Explosion-proof rating)
 - Valve for pre-humidification
 - Irrigation system pressure gauge
- 5) Water pressure regulator, solenoid valve, and Rota meter shall be provided for control of water application rates. These components shall be mounted in the water control cabinet.

k. Accessories

- 1) The direct reading Rota meter shall be a variable area type with a Teflon float, EPR "O" rings, and PVC fittings. The Rota meter shall be sized to the pipe and have a direct reading scale.
- 2) A nutrient containment and metering system shall be provided with the system. Nutrients supplied as a coating to the support media shall not be allowed.
- 3) All water and drain piping shall be SCH 80 PVC.

l. Nutrient Reservoir

The nutrient reservoir shall be integrated into the system sump. No loose external tanks shall be provided with the system.

3. CARBON MEDIA ODOR CONTROL UNIT

Stand Alone Activated Carbon Unit

- a. If required, the Contractor shall install a carbon media odor control unit in accordance with the engineering plans. The carbon media odor control unit shall meet the requirements of this specification.
- b. The unit shall have an AMCA certified centrifugal industrial fiberglass reinforced V-belt Arrangement No. 10 driven plastic fan equipped with undrilled inlet flange, outlet flange, Viton shaft seal, fan guard, and motor enclosure. Each fan and drive motor shall be mounted on a common base assembly designed for mounting on a concrete pad. The fan motor shall be high efficiency type, TEFC, and with a

1.15 service factor and matched to the electrical service at the standard lift station. Accommodation to accept a hand-held tachometer shall be available for each fan. Each fan shall have a drain with plug. The fan shall include graphite impregnation for grounding.

- c. The contractor shall complete the "TBDs" for the unit fan being proposed for the following maximum operating conditions:
- d. The unit shall have a fan sound attenuation package capable of reducing the sound level by a minimum of 25 dB which shall be placed over the fan and motor assembly. The doors shall be equipped with heavy duty hardware and with seals to minimize noise leakage. Stainless steel sheet flashing shall be provided to enclose the penetrations in the enclosure for the fan inlet and outlet ducting. The enclosure shall be fitted with louvered vents as required for heat dissipation/ventilation.
- e. The fan shall be factory wired to a stainless steel NEMA 4X panel. The panel shall have a fan control switch with a pilot lamp to indicate the fan running status. The power supplied to the panel shall be matched to the electrical service at the standard lift station. The panel shall be provided with a power disconnect switch, VFD, and control transformer. The fan speed shall be manually adjusted by the operating the VFD.
- f. The contractor shall provide the necessary ductwork between the fan ductwork and the adsorber vessel. The ductwork shall include a volume control damper with lockable louver for flow adjustment. The material of construction shall be same as that of adsorber vessel.
- g. The carbon adsorber vessel shall be constructed of non-corrosive polypropylene with a minimum thickness of 1/8" is required for a vessel diameter between 18" and 24" and a 1/4" thickness for vessel diameter up to 60" and designed for the following criteria:

Vessel Diameter, ft	TBD
Vessel Straight Side Height, ft	TBD
Internal Positive Pressure, in. WC	+15
Maximum Operating Temperature, °F	150
Carbon Bed Depth, ft.	3.0

- h. The carbon adsorber vessel shall have a differential pressure gauge to continuously monitor the pressure drop across the carbon bed. The differential pressure gauge shall be isolated with isolation valves and mounted on the vessel.
- i. The carbon absorber vessel shall have three (3) one (1") inch diameter sample probes per bed extending into the bed a minimum of twelve (12") inches. The sample probes shall be blocked off with a PVC ball valve.
- j. The carbon absorber vessel shall accommodate a single bed of

activated carbon having an average depth of three (3') feet. The carbon bed shall be supported on a polypropylene screen through an FRP support grating system. The screen and the support system shall be removable through the top cover. The top cover shall use quick release tie downs that are integral to the cover and not require the use of separate tools for the removal of the cover. The support system shall consist of removable grating. NOTE: Pall rings or other dumped packing media as a means of carbon support shall not be used. The support system shall be designed to withstand a load of at least 150 lbs/ft² with a minimum deflection of one quarter (1/4") inch under all conditions.

- k. The carbon absorber vessel shall have a "gooseneck" type outlet to prevent rainwater from entering into the system.
- l. The activated carbon media shall be virgin, pelletized, and derived from high grade bituminous coal vapor phase type suitable for the control of sewage odors. The carbon shall have the following specifications:

Iodine Number, mgI ₂ /g	1050 min
MPD, mm	3.9-4.1
Apparent Density, g/cc	0.46-0.52
Hardness No.	95 min
Butane Activity	26 min
H ₂ S Capacity, gH ₂ S/cc*	0.30 min

- * The H₂S breakthrough capacity is determined using ASTM standard method D6646-01. Prior to testing, the test sample shall be completely humidified by exposing the sample to a flow of humid air (>85% RH) for at least four (4) hours. Testing shall be accomplished by passing a moist (85% RH) stream of air containing one (1%) percent vol. H₂S and the selected concentration of CO₂ through a one (1") inch diameter tube with a nine-inch deep bed of closely packed carbon at a rate of 1,450 cc/min and monitoring to a 50 ppm H₂S breakthrough. The results shall be reported as grams of H₂S adsorbed per cc of carbon.
- m. All steel hardware shall be 316 stainless steel unless stipulated in this specification or on the engineering drawings. Gaskets shall be full face with a minimum of 1/8" thickness and made of EPDM or neoprene suitable for the intended service.
- n. The unit shall include a grounding rod with 10-gauge wire in accordance with current local, state and national codes.
- o. All other components and appurtenances shall be as specified on the engineering drawings and in the NPU standard details.

Optional secondary activated carbon polishing unit
 If the optional secondary activated carbon polishing unit is required,

the contractor shall provide, as a minimum, the major components as specified under the stand-alone unit section including the concrete pad, the vessel, the carbon media, the connecting duct work and all other appurtenances necessary for a fully operational odor control system in accordance with this specification.

4. APPROVED PRODUCTS

The following manufacturer is approved.

- Odor Control units shall be Siemens, or NPU approved equal.

2.3 MATERIAL

The materials used in this work shall be all new and conform to the requirements for class, kind, size and material as specified below and/or as provided in other sections of the contract documents.

All stainless steel shall be 316 austenitic, non-magnetic unless otherwise required.

A. WET WELL, ACCESS HATCH AND CONCRETE COVER AND SLAB

1. GENERAL

- a. Pre-cast circular concrete wet wells and the wet well concrete cover shall comply with the structural requirements of ASTM C478, Type II, acid resistant cement and shall attain a minimum compressive strength of 4,000 pounds per cubic foot in 28 days. The wet well pre-cast base section shall be monolithic with the bottom section of the wet well. The precast wet well top shall include the access cover frame.
- b. The wet well design shall assume a soil density of 130 pounds per cubic foot and a concrete density of 150 pounds per cubic foot and shall resist flotation under the conditions of an empty wet well and a groundwater level from the wet well base to the finished grade including a safety factor of 1.5.
- c. Cast in place concrete slab shall comply with ACI and ASTM standards. Concrete shall be ASTM C-150 Portland Type II 3,500 psi air entrained at six (6%) percent plus or minus one (1%) percent unless otherwise noted on the engineering plans. Fine aggregate shall be ASTM C33 and coarse aggregate ASTM C33 three quarter inch ($\frac{3}{4}$ ") maximum size. Reinforcing shall be ASTM A615 Grade 60 deformed bars and stirrups and Grade 40 ties, welded wire fabric shall meet the requirements of ASTM A185, and fabricated reinforcing steel shall be in accordance with ACI 315. Form lumber shall be in accordance with ACI 347 and shall be used with removable metal form ties, non-staining and moisture absorbing form

release agents, and stainless-steel dovetail anchor slots, and water stops as shown on the engineering drawings.

- d. The wet well shall be set on a number 57 stone base in accordance with section 901 "Coarse Aggregate" of the latest revision Florida Department of Transportation Standard Specifications for Road and Bridge Construction.
- e. The individual wet well sections shall fit together with interlocking tongue and groove joints. Four (4) foot diameter wet wells shall be sealed with a R-4 rubber gasket and six (6) foot or larger diameter wet wells shall be sealed with two (2) one and one half inch (1-½") butyl rubber or plastic wet wells joint seal squeezed in and out to verify sealing. The outside of the groove joints for all wet wells shall be covered with a continuous overlapping butyl rubber wrap a minimum of eight (8") inches wide.
- f. The wet well shall include elastomeric gasket(s) for all piping. The gasket(s) shall have a stainless-steel adjustable strap to seal the gasket to the pipe. An elastomeric gasket(s) with a stainless-steel adjustable strap to seal the gasket to the pipe shall be installed in all on site core bored holes.
- g. The outside surface of the wet well shall be covered with three (3) coats (black/red/black or color changes to allow NPU to verify multiple coats) of coal tar epoxy coating with a minimum dry film thickness of ten (10) mils per coat for a total of 30 mils dry film thickness. Subsequent coats shall be applied within 48 hours of the previous coat. The internal wet well coatings (including cover) shall be a polymorphic resin. Coatings shall be installed in accordance with the manufacturer's specifications.
- h. The wet well access hatches and frames shall be compatible with the lift-out rail system in accordance with the engineering drawings and approved shop drawings. The wet well access hatch and frame shall be aluminum with 316 stainless steel hinges, handles, and associated hardware in accordance with NPU standard details.
- i. The standard lift station influent piping inverts shall be a minimum of sixty (60) inches above the base invert.

2. APPROVED PRODUCTS

- a. The following access hatch and frame is approved:
 - Halliday S1R aluminum access door with, non-corrosive padlock bar.
- b. The following manhole and wet well surface coatings are approved.
 - IET System
 - Raven 405
 - Green Monster Liner (GML)

- Engineered Coating Solutions

B. DISCHARGE PIPING AND VALVES

1. GENERAL

- a. The discharge piping and valves shall be designed, constructed and installed in accordance with the best practices and methods and shall operate satisfactorily when installed as shown on the drawings. The piping and valves shall be supported to the wet well walls and above ground as shown on the engineering drawings and the NPU standard details. To avoid flooding, both the wet well top and concrete slab under the above ground piping shall be graded such that they are a minimum of six inches (6") higher than the surrounding grades.
- b. The piping and valves shall be furnished and installed in accordance with the NPU specifications for "Force Mains" and "Valves".

2. APPROVED PRODUCTS

The following aluminum clean-out coupler with cap and chain manufacturer is approved:

- Kamlock

C. WATER SERVICE

The contractor shall provide a water service as shown on the engineering drawings and NPU standard details. The service shall include the labor and materials for the tap at the water main source, polyethylene piping, fittings, backflow prevention device, spigot, mounting brackets and connectors, etc.

A separate water service is required for the odor control (if applicable).

D. FENCE AND GATES

The contractor shall provide and install fence and double eight (8) foot gates (total sixteen (16) foot width) with hold-backs, and wheels in accordance with the engineering drawings and NPU standard details. All the fencing and gate components shall be adequate to meet the required wind resistance loading.

E. DRIVEWAYS

The contractor shall construct a sixteen (16) foot minimum wide concrete driveway as shown on the engineering drawings and NPU standard details. The driveway shall include right-of-way culverts, if required. The driveway shall be graded such that stormwater is directed away from the

wet well top and above ground valves.

F. LANDSCAPING

The contractor shall provide landscaping, if required, in accordance with NPU Specification for Landscaping.

PART 3 – EXECUTION

3.1 GENERAL

- a. The contractor shall prepare the standard lift station site for construction. This shall include the establishing of maintenance of traffic, surveying, site clearing, installation of silt fence, exposure of existing underground utilities, and notification of residences that may be impacted by the construction. The standard lift station wet well and concrete cover and slab, valves, piping, pump/motor assemblies and rails, control panel, water service(s), electrical wiring/conduit, pad, fencing and gates, access panel and frame, driveway/culverts, optional equipment, and accessories shall be installed in accordance with the contract documents.
- b. Installation shall be made by skilled and licensed technicians and coordinated with other trades as necessary.
- c. The standard lift station receives wastewater flows continuously at varying rates and the level of the flow in the wet well is monitored by a radar level transmitter. The wet well radar level transmitter shall transmit the level of the wastewater in the wet well directly to the control panel. The level transmitter shall be set for the following conditions in coordination with NPU operational personnel and the design of the station:
 - Pump off
 - Pump on
 - Lag pump on
 - High liquid level alarm
- d. The control panel is an integrated system. The contractor shall furnish and install it as one complete package to include all equipment and appurtenances regardless of the manufacturer and shall be responsible that it performs as a fully integrated operable system.

The control panel shall be designed to provide the following functions:

- Turns pump off
- Turns pump on
- Turns lag pump on
- Provides for alternate pumps operation
- Activates the audio and visual alarms in the event of high liquid wet

well levels

- Activates the battery backup high liquid level alarm in event of power loss and resets the alarm when the power is restored.
- Provides phase monitoring and protection
- Monitor and indicates pump seal failures

The applicable functions shall be transferred to the TCU/PLC unit to control as outlined in the TCU section.

- e. The TCU shall be designed to provide the following functions:
- Lead/Lag: One pump operates as the lead or in-service pump and one acts as the lag or backup pump. The PLC alternates the lead and lag pump at operator settable intervals as required.
 - Monitors lift station operational status and notifies NPU personnel of normal and abnormal operations such as, but not limited to: status of power, generator operations, pump trip, high/low alarm levels in the wet well discharge flow, and records pump run time and pump starts.
 - Pump on, Pump off
 - High level, Low level
 - Phase Voltage
 - Liquid Level Control Sequence

Refer to NPU standard details for the complete list of functions.

- f. The contractor shall coordinate the work of all of the sub-contractors, suppliers, manufacturers, etc. for the complete installation, integration, interconnection, testing, calibration, and startup of the instruments, sensors, controls, and related accessories.
- g. The contractor shall provide for all temporary utilities and services required for operations including but not limited to electrical power, water, sanitary facilities, etc. The contractor shall furnish, install, and maintain all temporary utilities and services during the contract period including removal and restoration of disturbed areas upon completion of the work. Such facilities shall comply with regulations and requirements of the National Electrical Code, OSHA, Florida Power and Light, and applicable Federal, State, and Local codes, rules, regulations and in accordance with NPU specifications.
- h. The contractor shall be prepared to maintain wastewater flow as a part of operations and provide all pumps, piping, and other equipment to accomplish this task, perform all construction, obtain all permits, pay all costs as applicable, and perform complete restoration of all existing facilities to equal or better condition to the satisfaction of NPU in accordance with NPU specifications.

3.2 INSTALLATION

- a. Grounding rods shall be provided to adequately and independently ground the panel, standby generator, TCU, and odor control in accordance with the contract documents. A grounding loop with a single ground rod may be substituted if approved by NPU.
- b. The contractor shall connect the biofilter unit to the lift station water supply in accordance with the engineering drawings.
- c. All wire ends shall be identified with wire markers at both ends.
- d. All instrumentation wiring shall be shielded from a continuous source to destination and shall be grounded in accordance with the manufacturer's recommendation.

3.3 BEDDING, BACKFILL, AND COMPACTION

- a. All bedding, backfill and compaction shall meet the requirements of NPU Standard details and specifications.

3.4 CALIBRATION

The contractor shall ensure the following:

- a. The instruments shall be calibrated by the manufacturer in accordance with the contract documents.
- b. A calibration sticker noting the date, calibration data and the technician's initials shall be affixed to the instrument. A calibration data sheet and log shall be prepared for NPU.

3.5 TESTING

- a. The contractor shall not initially energize the equipment without the approval of NPU.
- b. After installation and calibration, the contractor shall functionally test the major equipment and electrical components to verify their compliance with the manufacturers recommended specifications and the contract documents.
- c. The contractor shall not activate or turn on any equipment until each control circuit has been red-lined for completeness and functionality and safety interlocks are tested.
- d. The contractor shall document site testing activities by written test procedures and a testing log shall be maintained at the project site or given to NPU.
- e. Wet well exfiltration test shall consist of plugging all inlets and outlets, filling the wet well with water to the rim of the structure, and letting the water remain for 24 hours. The water level is returned to the top of the rim and let stand for two (2) hours. No leakage shall be allowed for the test to pass.

3.6 START-UP OPERATIONS

- a. The system integrator/supplier shall provide equipment startup services for the project.
- b. The system integrator/supplier shall be responsible for providing factory trained representatives for the startup of equipment requiring factory assistance during startup.
- c. The system integrator/supplier shall coordinate with NPU to assist with the startup activities and provide necessary training of NPU personnel in the operation and maintenance of the system.
- d. Upon construction installation of NPU -maintained standard lift stations, startup operations and testing shall be conducted prior to final acceptance and release of wastewater flows under the supervision of the NPU Engineering Department. At a minimum, a representative of the pump Supplier, a representative of the Contractor, and a representative of NPU will be present for startup testing. An "NPU Lift Station Startup Check List", shall be completed and signed off in entirety before a facility shall be accepted by NPU.

3.7 SPARE PARTS

Per each lift station, the contractor shall provide on or before the final inspection.

- a. Fuses for the panel
- b. Two spare impellers with wear rings, one upper and lower bearings, o-rings, one set of upper and lower shaft seals
- c. Spare VFD (if VFDs are used at that lift station)

3.8 TECHNICAL MANUALS

- a. The contractor shall provide operation and maintenance data in the form of an instructional manual. The manual shall be in an electronic submission via a flash drive and a three-ring binder and be arranged in sections and include a table of contents. The manual shall include appropriate drawings, schematics, pictures, sketches, specifications, flow diagrams, manufacturer's documents, etc. required to operate and maintain the individual standard lift station functions and the overall standard lift station as a system.
- b. One (1) electronic copy, via flash drive, of the O&M manuals shall be made available to NPU 30 days prior to the standard lift station start-up for review prior to start up. Upon NPU and Engineer validation, the contractor shall provide one (1) electronic copy of the approved O&M manuals including copies of certified tests and inspection data, via flash drive.

END OF SECTION

EXHIBIT C-1 TO CONTRACT NO. 2023-34

FEE SCHEDULE

<u>No.</u>	<u>Description</u>	<u>Unit</u>	<u>Item Cost (3)</u>
<u>REPAIR</u> (1)	-	-	-
	See Note 4 below		
1	Six (6') foot 2.875" OD Steel Corner Post including caps	EA	\$25.00
2	Six (6') foot 2.375" OD Steel Line Post including caps	EA	\$23.00
3	Six (6') foot 4.0 OD Steel Gate/Corner Post including caps	EA	\$94.00
4	Eight (8') foot 2.875" OD Steel Corner Post including caps	EA	\$34.00
5	Eight (8') foot 2.375" OD Steel Liner Post in caps	EA	\$31.00
6	Eight (8') foot 4.0 OD Steel Gate/Corner Pose including caps	EA	\$125.00
7	Top Rail and ties	LF	\$2.50
8	PVC Fence Fabric, two (2") inch mesh, Six (6') Foot including tension bar and tension wire (1)	LF	\$4.20
9	PVC Fence Fence Fabric, two (2") inch mesh, Eight (8') Foot including tension bar and tension wire (1)	LF	\$5.59
10	PVC Fence Fabric, one (1") mesh, Six (6') Foot including tension bar and tension wire (1)	LF	\$14.00
11	PVC Fence Fabric, two (1") mesh, Eight (8') Foot including tension bar and tension wire (1)	LF	\$16.00
12	Six (6') swing gate	EA	\$700.00
13	Four (4') foot padlockable pedestrian gate	EA	\$450.00
14	Twenty (20') rolling gate	EA	\$1,975.00
15	Three strand barbed wire	LF	\$0.55
16	Electrical Grounds	EA	\$25.00
17	Complete new lift station fence installation, forty (40') by forth (40')	EA	\$10,278.00
18	Eight (8') foot swing gate	EA	\$850.00

Note 1	The minimum linear footage for fence fabric will be ten (10') feet.
Note 2	Quantities shown are for illustrative purposes and to establish a unit price for each specific item and do not necessarily represent the quantities of any specific work assignment that might result from this solicitation.
Note 3	If renewals of the contract are executed the unit prices shall be increased by the most recent 12-month percentage change All Items, as published by the United States Department of Labor, Bureau of Labor Statistics, https://www.bls.gov/cpi/.
Note 4	All materials shall be in compliance with 321040 of the Specifications and Details in this procurement
Note 5	Removal and disposal of any existing fence is incidental to the new or repaired fence construction and there is no separate bid item for existing fence removal and disposal. Cost should be included in each line item.
Note 6	The cost of clearing, removing and disposing of the material shall not constitute a separate bid item and shall be considered incidental to fence construction/repair.